

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

SECTION

For corners in

Roscommon (County)	Located In:	Corner Code #/
	<u>Rosco</u>	<u>L - 1</u>
1. Public Land Survey	T <u>24N</u> R <u>4W</u>	<u>L - 13</u>
	T <u>25N</u> R <u>4W</u>	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

28 DEC 99 3:02 P.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

LIBER 4 PAGE 71

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, Marvin E. Myers, in a field survey on June 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. - 1852	Robert T. Ostling R.L.S.	Frank J. Arleth, P.S. #21266
Geo. H. Cannon, D.S.	Map of Alignment survey for	Unrecorded alignment survey May 29, 1966
Mon.-Post	Roscommon County Road Commission	Mon: Found 2" pipe
Wit: Birch N23 1/2°E 26 lks.	Date: 7-20-51	Wit: placed bar & cap #21266 East 28.1'
7" Black Oak N51 1/2°W 34 lks.	Mon: Found 2" pipe in concrete base	placed bar & cap #21266 North 20.0'
	set from remains of BT's	
	Wit: Spike in 14" Red Oak N37°W 55.96'	
	Spike in 14" Oak N26 1/2°E 57.0'	
	Spike in 8" Oak S1/2°E 37.6'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" pipe of record in South edge of gravel (Forest Avenue) and in the centerline of a fire lane North  
Found bar & cap #21266 East 28.1'  
Found bar & cap #21266 North 20.0'  
Accepted pipe as a perpetuation of the original Government corner. Replaced pipe with Standard Roscommon County Monument.

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE SEPT 10, 1999

Marvin E. Myers M.E.M.  
Marvin E. Myers, P.S.  
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon: Standard County Corner  
Wit: Set nail in NW face 20" White Pine N35°W 33.76'  
Set nail in N. face 16" Black Oak N60°E 80.44'  
Set nail in NE face 18" Ash S14°E 19.15'  
Set nail in e. face 26" White Pine S46°W 50.67'  
Set Carsonite Post 30' North



Signed by Marvin E. Myers  
Surveyor's Michigan License No. 31600

Date NOV 27, 1999