

MAR 22 1999

LIBER 3 PAGE 335

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

For corners in

Crawford  
(County)

Located in:

Corner Code #

29 SEP 98 10:01 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

- 1. Public Land Survey T 25N R 4W M-4 ✓  
T 25N R 3W A-4  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on JULY 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O - 1839 John Brink, DS
- Mon. - Post
- 14" Y. Pine S4°W 133 lks.
- 7" S. Pine N24°W 106 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar 1.5 feet deep 2± West of centerline of South Oak Road. On treeline West. A-3 is North 2628.12. A-5 is S00°00'43"W 2628.62. Accepted 1/2" rebar as the best available evidence of the position of the Original Corner. Replaced 1/2" rebar with standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon - Standard Crawford County Monument.
- Wit: Nail & tag in North side of Power Pole N86°W 29.09
- Set nail & tag in SW side 24" White Oak N25°W 97.38
- Set nail & tag in SW side 8" White Oak N55°E 74.23
- Set nail & tag in NE side 12" Red Oak S24°E 86.18
- Set Carsonite Post East 33.00

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Aug 21, 1998  
*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Marvin E. Myers*  
Surveyor's Michigan License No. 31600

Date Aug 24, 1998