

MAR 22 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

For corner in SECTION

Crawford
(County)

Located In:

Corner Code #

29 SEP 98 10:01 A.M.

- 1. Public Land Survey T 25N R 4W
T 25N R 3W
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

M-5
A-5

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Marvin E. Myers, in a field survey on July 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Numbers 1-36 are placed in the grid cells.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O - 1839 John Brink, DS Mon. - Post 14" Y. Pine S4°W 133 lks. 7" S. Pine N24°W 106 lks.
GLO 1852 Mon - Post 18" Y. Pine N10°E 112 lks. 14" Y. Pine S75°E 199 lks.
Apr 1959 Jerome B. Seward Survey Chief MSHD Mon - 1" Pipe 20" N. Pine N75°W 55.95 18" N. Pine N55°E 48.62 16" N. Pine S59°E 43.66
L1,P166 LCRC May 14, 1971 C.E. Ostling 12026 Mon - Pipe 16" N. Pine N56°30'E 48.2 14" N. Pine S77°E 43.5 18" N. Pine S74°W 70.9
July 1976 G.D. Henning RLS 2240 Mon - Not given 1/2" Bar N89°30'12"E 33.00 16" N. Pine N56°30'E 48.2 14" N. Pine S77°E 43.5 18" N. Pine S74°W 70.9

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found Pipe in East shoulder of South Oak Road & Centerline of 6 Mile Road to the West. Found 16" stump S56°E with spike & Henning tag 43.60(M) 43.5(R) Accepted as the best available evidence of the Position of the Original Corner. Replace Pipe with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon - Standard Crawford County Monument.
Wit: Set Carsonite Post East 5±
Found Henning nail & tag S56°E 43.60
Set nail & tag in South side of 12" J. Pine with old blaze on face N84°E 36.14
Set nail & tag in SW side 14" Norway S57°E 54.93
Set nail & tag in NW side 10" Norway S56°W 41.57
Set nail & tag in NE side 12" Jackpine N42°W 45.78



Signed by [Signature]
Surveyor's Michigan License No. 34680

Date Aug 24, 1998

CRAWFORD COUNTY
PEER GROUP APPROVAL

DATE Aug 21, 1998

[Signature]

Marvin E. Myers, P.S.
County Surveyor