

MAR 22 1999

LIBER 3 PAGE 333
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>25N</u> R <u>4W</u>	<u>M-6</u> ✓
	T <u>25N</u> R <u>3W</u>	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

29 SEP 98 10:01 A.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on July 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1839 John Brink, DS
Mon. - Post
8" S. Pine S14°W 16 lks.
8" S. Pine N22°W 30 lks.

July 1976 G.D. Henning RLS 2240
Mon - 5/8" Bar
1/2" Bar N89°49'28"E 33.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" bar. 1/2" bar N89°49'28"E 33.00 Accepted as best available evidence of the position of the Original Corner. Replaced 5/8" bar with Standard Crawford County Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon - Standard Crawford County Monument.
Wit: Found 1/2" bar N89°49'28"E 33.00
Set nail & tag North side 24" Black Oak N80°E 28.65
Set nail & tag East side 6" Black Oak N03°W 26.66
Set nail & tag in South side 4" Jackpine S74°W 33.06
Set Carsonite Post West 1±

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Aug 21, 1998

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Aug 24, 1998