

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 N. R. 4 W.	C-7; D-7
2. PROPERTY CONTROLLING IN SECTION 17 _____	T. 25 N. R. 4 W.	15; 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 25, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - Description of original monument and accessories and/or subsequent restoration:

- C. (continued)
- | | |
|----------------------|--------|
| | 16 |
| Set 5/8" Rod | |
| 14" R. Pine S55°E | 106.35 |
| 8" J. Pine S28°W | 60.81 |
| Cedar Post Southwest | 45 |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-7 Found 2" pipe at road intersection, probably as established in old Schaaf survey. Considered acceptable.
- D-7 Found 2" pipe 3' south of centerline of E-W road, used in previous surveys in this area.
- 15 Set corner by standard survey procedure for the subdivision of sections.
- 16 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7	D-7	15
Fd. 2" pipe in conc. & set DNR monument	Fd. 2" Pipe-Set DNR Monument Nail & ref.tag in 14" W.Oak	Set 5/8" Rod w/RLS Cap
6" J. Pine N26°E 108.64	S63°W 59.8	3" J. Pine S30°W 35.05
Nail in PP N51°W 51.32	Nail & ref.tag in 8" J.Pine	5" J. Pine S19°E 43.72
Cedar Post South 40	S08°E 56.25	Cedar Post South 27
	Cedar Post Southeast 40	

SIGNED BY Kenneth J. Ostling DATE 11-15

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY