

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 N. R. 4 W.	G-5; G-6
2. PROPERTY CONTROL- ING IN SECTION 16	T. 25 N. R. 4 W.	3; 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 16, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - Description of original monument and accessories and/or subsequent restoration:

C. (continued)

16

Set 5/8" Rod w/RLS Cap	
9" R. Pine N30°W	61.22
4" R. Pine N25°E	55.0
Cedar Post North	


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-5 Set corner by single proportionate measurement between section corner south and original ¼ corner North (between 9 & 10). No original evidence.
- G-6 Set corner by proportionate measurement between section corners. Unable to identify U.S. evidence.
- 3 Set by standard survey procedure for the subdivision of sections.
- 16 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5	G-6	3
Set DNR Mon. & cedar post	Set DNR Mon. & cedar post	5/8" Rod w/RLS Cap & cedar post
6" Maple S54°W 16.25	12" R. Pine N73°E 12.0	6" Maple N54°E 3.24
7" Maple N04°E 6.53	9" R. Pine N18°E 36.0	12" Oak N76°W 11.94

SIGNED BY *Kenneth J. Ostling* DATE 11-16-78
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY