

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 25 N. R. 4 W.	E-6; E-7; F-5; F-7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
 FILING NUMBER _____

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 16, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - ~~Description of original monument and accessories and/or subsequent restoration~~
 C. (continued)

F-7		
Set DNR Mon. in place of ½" bar		
6" R. Pine	N35°E	75.45
8" R. Pine	N33°W	81.34
Cedar Post	North	40

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-6 Set corner by proportionate measurement, midpoint on line, between section corners. No previous corner.
- E-7 Found ½" bar in concrete tile and 2" pipe in centerline E-W road as established in previous survey. Considered acceptable.
- F-5 Set corner by proportionate measurement between section corners. No original evidence.
- F-7 Found ½" bar in centerline of E-W road as previously established by early surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6	E-7	F-5
Set DNR Mon. & Cedar Post	Set DNR Monument	Set DNR Monument & Cedar Post
5" W. Oak N18°E 21.7	16" W. Oak N06°E 71.0	5" W. Oak N76°W 1.55
10" Maple S73°E 31.8	8" R. Pine S62°E 99.95	6" W. Oak N11°W 16.55
	Cedar Post North 40	

SIGNED BY _____

Kenneth Ostling

DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CRAWFORD COUNTY