

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CRAWFORD

(County)

Located in:

Corner Code ##

1. Public Land Survey	T	<u>25N</u>	R	<u>4W</u>	<u>K-9</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	<u>25</u>	T	R	<u>1, 2</u>
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL F. ROSER, in a field survey on JULY 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES AND TOPOGRAPHY AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>K-9</u>	<u>1</u>	<u>2</u>
FD IRON FOR NW COR 5-25 AS SET BY P.S. N.PARKER IN 1979 SURVEY. CORNER IS IN NE QUAD OF FLETCHER ROAD (E-W B.TOP) AND US 27 EXPRESSWAY, ON BRIDGE FILL.	FD 1/2" REROD FOR NW COR OF NE 1/4 OF NW 1/4 SEC. 25. COR BY P.S. N.PARKER CERT OF SURVEY DATED NOV 14, 1979 & RECORDED LI 183, PG 283. COR IS IN LINE W/CTR OF TRAIL N & 21' N OF CTR E-W B.TOP.	ESTABLISHED NE COR OF NW 1/4 OF NE 1/4 OF SEC 25 PER STANDARD BLM INSTRUCTIONS. COR IS IN APPROX LINE W/CTR OF TRAIL N & 7' N OF CTR E-W B.TOP.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

<u>K-9</u>	<u>1</u>	<u>2</u>
FD CAPPED IR #16939. (ALL DIST ARE SLOPE DISTANCES)	FD REROD 1/2" X 24".	SET 5/8" X 32" REROD W/CAP IN E-W BLACKTOP ROAD.
GUARD RAIL POST S46°E 23.74'	1 8" J PINE N36°W 39.50'	POWER POLE N46°W 34.70'
GUARD RAIL POST S54°W 25.76'	1 8" OAK N86°E 24.70'	7" J PINE S33°W 45.10'
4" R PINE N02°W 14.77'	5" J PINE N65°W 50.78'	10" RED PINE S05°E 43.42'
1 18" J PINE N63°E 44.52'	N EDGE BIT RD. SOUTH 11.0'	12" RED PINE N30°E 68.99'
	FD B.SPIKE S03°07'W 21.64'	N EDGE BLK TOP NORTH 2.82'
1N.PARKER WITS.	1N. PARKER WITS.	FD 1 1/2" IR PIPE (M.SCHAFF MON) S08°E 11.4'



Signed by Carl F. Roser

Date 6-29-95

Surveyor's Michigan License No. 12028

