

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Crawford Located In _____ Corner Code # _____
(County)

1. Public Land Survey		T	<u>25N</u>		R	<u>4W</u>		<u>L-3</u>
		T	_____		R	_____		_____
2. Property Controlling in Section	S	1	T	<u>25N</u>	R	<u>4W</u>		<u>16</u>
	S	_____	T	_____	R	_____		_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____		_____
	S	_____	T	_____	R	_____		_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on January 25, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3												●	●
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-3 GLO Addison P. Brewer set post for quarter corner
Wits. Hemlock 8" N30°W 14 links
W. Birch 10" S44°E 26 links

16- Liber 255, Page 187 (1986) Norman F. Parker
P.S.#16939 set 1/2" bar for corner.
No witnesses given.

Liber 149, Page 253 (1975) C. Eugene Ostling
P.S.#12026 found 1/2" bar for South 1/4 corner of section 1.
Wit: 30" W. Pine S38°E 64.8'
18" R. Oak S35°W 61.0'

Liber 255, Page 187 (1983) Norman F. Parker P.S.#16939
fd 1/2" bar for corner.
Wit: 32" W. Pine S38°E 64.8'
18" Oak S35°W 61.0'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L-3 Found 1/2" bar added P.S. cap #33981

16- Found 1/2" bar added P.S. cap #33981

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 1/2" iron rod w/ P.S. cap #33981
Wit: 32" W. Pine S29°E 66.28'
16" Oak S43°W 61.70'
fd 3/4" pipe N7°E 32.92'
P.Pole N1°W 30.95'
7" W. Pine N46°E 90.74'
Blue Carsonite Post South 33'

16- 1/2" iron rod w/ P.S. cap #33981
Wit: 16" W. Pine S34°W 57.16'
5" W. Pine S26°E 43.89'
P.Pole N69°E 66.47'
6" W. Pine N11°E 34.37'
Blue Carsonite Post North 33'

Signed by: _____

Carl T. Kiiskila

Date: _____

2-8-05

Surveyor's Michigan License No.: _____

33981

