

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Crawford (County)	Located In	Corner Code #
1. Public Land Survey	T <u>25N</u> R <u>4W</u>	<u>L-2</u>
2. Property Controlling in Section	S <u>1</u> T <u>25N</u> R <u>4W</u>	<u>9</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on January 25, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-2 Liber 149, Page 253 (1975) C. Eugene Ostling
P.S.#12026 set 1/2" bar for the center of section 1.
Wit: 20" W. Birch S33°45'E 39.45'
8" R. Pine S74°45'W 78.00'
24" Poplar N23°W 111.9'

9- This corner position was not established during the original government survey.

Liber 214, Page 380 (1983) Norman F. Parker P.S.#16939
Fd 1/2" bar as set by C. E. Ostling. Same witnesses as above.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L-2 Found 1/2" iron rod as set C. E. Ostling.

9- Established the Northeast corner of the Northwest quarter of the Southeast quarter of section 1 as per B.L.M. instruction for the subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-2 1/2" iron rod
Wit: 4" Maple S25°E 42.03'
8" Oak S43°W 41.93'
Fence post N12°E 25.94'
1/2" iron rod w/ P.S. cap S6°W 32.97'
18" R. Pine S86°W 78.69'
Blue Carsonite Post South 33'

9- Set 5/8" Rerod with P.S. cap #33981
Wit: 7" Oak S54°W 42.12'
8" Cherry N32°W 27.38'
6" Poplar S6°W 51.13'
8" Cherry N67°E 57.82'
Pin falls in centerline of East - West road.
Blue Carsonite Post South 33'

Signed by: _____

Carl T. Kiiskila

Date: _____

2-8-05

Surveyor's Michigan License No.: 33981

