

CRAWFORD COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CRAWFORD

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>26N</u> R <u>1W</u>	<u>A - 8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED FOR RECORD THIS
27 DAY OF Dec, 1993 AT
7:00 am/pm, IN LIBER 3
PAGE 118

Elizabeth D. Wisland
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - April 1839 J. Mullett Mon. - Post WIT: 8" Pine S13°W 23 lks. 8" Pine N52°W 34 lks.	L.224, pg.558 Consumers Power Co. Mon. - Fd. 1" Rebar WIT: Power Pole N80°W 39.07' Post East 1.00'	Mon. - 5/8" Bar M.E.Myers WIT: Fd. nail & tag N. side Power Pole N80°W 39.07' Post with tag N. 0.60'± PK nail W. side 4" J.Pine N20°E 6.30' PK nail SE side 2" J.Pine N60°E 11.05' PK nail SW side 5" J.Pine S15°E 7.04' 5/8" Bar West 35.20'
---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" bar verified location by measurement to accessories and corners of record and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Set in exact location Std. Crawford County Monument
WIT: Fd. PK nail in W. side 5" J.Pine N20°E 6.30'
Fd. PK nail SE side 3" J.Pine N60°E 11.05'
Fd. Pole barn nail in Sw side 5" J.Pine S15°E 7.04'
Fd. nail & tag N. side Power Pole N80°W 39.07'
Fd. 5/8" Bar West 35.20'



Signed by Marvin E. Myers Date December 21, 1993
Surveyor's Michigan License No. 31600

202A