

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

CRAWFORD COUNTY


T 26 N R 1 W
T 27 N R 1 W

DESCRIPTION OF CORNER Sec. corner common to Sections 2-3-34-35

CORNER MONUMENT Nat. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 8-19-70

WITNESSES TO CORNER..... 8" J. Pine N 69 E 55.1'



7" J. Pine S 33 W 25.9'

*22" R. Pine S 20 E 128.8'

AND

* Fargo witness tree

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a survey of Section 3. Found Schaaf pipe with concrete block, about 6' South of position prescribed by witness pits. Schaaf record claims to have remains of USBS, and this corner was used in 1951, Section 2 subdivision by Henning.

Fargo corner is located S 15 E 20.7'.

SURVEYOR'S SEAL

SIGNED *Donald H. Kellogg* DATE 8-26-70
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing