

APR 27 1995

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 22, 1994

LIBER 3 PAGE 157

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                       |                         |               |
|---------------------------------------|-------------------------|---------------|
| Crawford<br>(County)                  | Located In:             | Corner Code # |
| 1. Public Land Survey                 | T 26N R 3W              | B - 3         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                         |               |
| 5. Private Claims _____               |                         |               |

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
30<sup>th</sup> DAY OF Dec, 1994 AT  
4:20 am/pm IN LIBER 3  
PAGE 157.

*Elizabeth W. Wiland*  
Register of Deeds Stamp & File Number

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 4  |    |    |    |    |    |    |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 16 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Marvin E. Myers, in a field survey on December 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-A.P. Brewer 1852  
Mon-Set Post  
WIT: 12" S.Pine N05°W 26 lks.  
10" S.Pine S26°E 65 lks.
- N. Parker Aug. 22, 1977 L.165, pg. 402  
Mon-Iron in pav't box in C I-75  
Business Loop  
WIT: None
- N. Parker Mar. 9, 1981 L.194, p. 375  
Mon-3/4" Pipe in Mon. Box  
WIT: MDSH Tag in 8" Elm N48°E 57.0'  
MDSH Tag in P.Pole S41°E 46.45'
- R. Ostling-Date unknown  
Mon-Nail & Tag in Hwy. C  
WIT: None
- K. Ostling Sept. 7, 1977 L.163, pg. 234  
Mon-3/4" Pipe in Mon. Box  
WIT: MDSH Tag in 8" Elm N48°E 57.0'  
MDSH Tag in P.Pole S41°E 46.45'
- N. Parker Apr. 28, 1981  
Mon-Iron in MDSH Mon. Box  
WIT: None
- N. Parker May 19, 1972 L.2, pg.95  
LCRC  
Mon-Fd. 3/4" Pipe in C Old US 27  
and N. Down River Rd.  
WIT: None
- N. Parker Apr. 13, 1978 L.168, pg.562  
Mon-3/4" Pipe in MSDH Mon. Box  
WIT: None
- N. Parker Jan. 5, 1982 L.204, pg.88  
Mon-3/4" Iron in Mon. Box  
WIT: MDSH Tag in 8" Elm N48°E 57.0'  
NDSH Tag in P.Pole S41°E 46.45'
- N. Parker Oct. 31, 1985 L.240, pg.74  
Mon-3/4" Iron in Mon. Box  
WIT: None
- M.E. Myers  
Mon-3/4" Pipe in Mon. Box  
WIT: MDSH Tag in 8" Elm N48°E 57.0'  
MDSH Tag in P.Pole S41°E 46.45'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found 1/2" x 18" Iron Bar with 1/2" ID x 2" Iron Pipe on top of bar in Mon. Box in centerline intersection North Down River Road and I-75 Business Loop  
WIT: Fd. nail NW side 16" Elm N50°E 57.05'  
Fd. nail NW side U.Pole N70°E 66.48'  
Fd. nail NE side U.Pole S45°E 53.92'  
Fd. "MDSH ref. point" nail & tag SE side U.Pole S43°W 54.94'  
Fd. nail NE side U.Pole N42°W 46.22'  
Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set Std. Crawford County Mon. stamped "T26N R3W B-3 31600" in Mon. Box in exact location of 1/2" bar  
WIT: Fd. nail NW side 16" Elm N50°E 57.05'  
Fd. nail NW side U.Pole N70°E 66.48'  
Fd. nail NE side U.Pole S45°E 53.92'  
Fd. "MDSH ref. point" nail & tag SE side U.Pole S43°W 54.94'  
Fd. nail NE side U.Pole N42°W 46.22'



Signed by Marvin E. Myers

Date Dec 29, 1994

Surveyor's Michigan License No. 31600