

APR 27 1995

COMMISSION

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE 12-29-94

LIBER 3 PAGE 167

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| Crawford (County) | Located In: | Corner Code # |
|---------------------------------------|----------------------------|---------------|
| 1. Public Land Survey | T <u>26N</u> , R <u>3W</u> | B-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN

COUNTY OF CRAWFORD

FILED FOR RECORD THIS
30th DAY OF Dec, 1994 AT
4:20 am (pm) IN LIBER 3
PAGE 167

Elizabeth S. Williams
Register of Deeds, Stamp & File Number
Register of Deeds

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|----|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | ● | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 |
| 6 | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |

I, Marvin E. Myers, in a field survey on Dec 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- GLO-A.P. Brewer (1852)
- Mon- Set Post
- Wit-11" Spruce N33°W 16 lks
- 10" Tamarack S62°E 2 lks
- R. Ostling Aug 11-1959
- Mon- 1/2" x 24" Bar
- Wit- 5" Cedar N55°E 3.7
- 5" Cedar S19°E 11.4
- 5" Cedar S75°W 7.0

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" x 24" bar laying on side 2.5± NE'ly of 3"x32" Cedar Post. Verified Position by Measurement to R. Ostling witnesses all intersect on the Cedar Post.
Accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Mon-Set standard Crawford County Monument marked cap "31600, T26N, R3W" in exact location of Cedar Post.
- Wit-Set nail & tag E. Side 6" Cedar N21°E 36.48
- Set nail & tag N. side 4" Cedar N85°E 13.03
- Set nail & tag SE side 12" W. Pine S34°W 59.54
- Set Carsonite Post S85°E 3.57



Signed by Marvin E. Myers

Date Dec 29, 1994

Surveyor's Michigan License No. 31600