

APR 27 1995

COMMISSION

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 22, 1994

LIBER 3 PAGE 160

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> , R <u>3W</u>	<u>C-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN

COUNTY OF CRAWFORD

FILED FOR RECORD THIS

30<sup>th</sup> DAY OF Dec, 1994 AT

4:20 am/pm, IN LIBER 3

PAGE 160

*Elizabeth Wilcox*  
Register of Deeds Stamp & File Number  
Register of Deeds

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	●	8	9	10	11	12					
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, Marvin E. Myers, in a field survey on Dec 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO- A.P. Brewer 1852 L201, P352 N. Parker 9-17-1981  
 Mon- Set Post Mon- Concrete Mon at Fence corner  
 Wit- 12" W. Pine N86°E 12 lks Wit- BT. 8" B. Oak S75°E 36.9  
 8" Y. Pine N77°W 18 lks N Cor. of Shed foundation S20°W 59.0  
 R. Ostling date unknown  
 Mon- Concrete tile Mon ( Houghton)  
 Wit- none given  
 N. Parker L. 156, P389 Nov 9, 1976  
 Mon- Conc. Mon.  
 L174, P386 N. Parker 11-9-1978  
 Mon- Concrete tile Monument  
 Wit- none given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 5" x 34" Concrete tile monument at fence line intersection; found 15" B. Oak S84°E 36.7 to face; N. corner shed foundation S12°W 59.05  
 Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 MOn-Set standard Crawford County Monument marked cap "31600".  
 Wit-Found 15" B. Oak S84°E 36.7 to face  
 Set nail & tag S. side 15" B. Oak S84°E 37.37  
 North Corner Shed foundation S12°W 59.05  
 Set nail & tag SE side Utility Pole N48°E 95.90  
 Set carsonite post N83°E 1.82



Signed by Marvin E. Myers  
31600

Date Dec 29, 1994

Surveyor's Michigan License No. \_\_\_\_\_