

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

For corners in

CRAWFORD
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 26N. R 3W C-6
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

FILED FOR RECORD THIS
5th DAY OF Jan 1994
11:15 AM, IN LIBER 3 PAGE 130
4c

John D. Williams
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 3 PAGE 130

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO- 1852 A. Brewer Mon- Post Wit- 10" S. Pine N70°E 25 lks 9" Y. Pine S47°W 15 lks June 1961 C.E. Ostling Mon- 1/2" Bar Wit- none given	LCRC L1, P146 May 1971 C.E. Ostling Mon- 1/2" iron Wit- 6" J. Pine N57°W 39.3 12" J. Pine Stump S69°W 54.8 LCRC L2, P307 July 1989 C. Lindgren Mon- Nail in pavement 0.2 below surface Wit- P.Pole S55°W 41.97 Chisled Hole in conc for flag pole N30°W 70.92 Top of Fire Hyd. S70°E 103.88 P.I. Boat Spike N05°E 41.09	LCRC L3, P45 Aug 1991 M.E. Myers Mon- Nail in Pavement Wit- Fd. Nail & MDOT tag NW side P.Pole S60°W 41.98 Top Center of Fire Hydrant S65°E 103.88 Center of Flag Pole N30°W 71.54 Nail in North side Telephone Pole N70°E 142.76 L156, P275 Aug 1976 N. Parker Mon- Not given Wit- Nail in NW side of P. Pole S65W 42.0 Face of Flag Pole N27°W 71.4 L176 P168 Mar 1979 N. Parker Mon- 1/2" bar Wit- Same as L156, P125
MDOT- I-75 BL Project 20012C Mon- 1/2" bar Wit- Not given L166 P125 Dec 1977 N. Parker Same as L156 P125 L232 P246 Jan 1985 N. Parker same as L256, P125	L174 P190 Sept 1978 N. Parker Same as L256 P 125	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
 Found 1/2" bar with cabin spike over top in pav't box verified position by measurment to accessories of record and accepted as the best available evidence of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon- Set Standard Crawford County 2"x21" monument.
 Wit- Nail & MDOT tag. NW side P.Pole S60°W 41.98
 Top Center of Fire Hydrant S65°E 103.88
 Center of Flag Pole N30°W 103.88
 Nail in North side Telephone Pole N70°E 142.76
 Corner is in Center line of South Bound I-75 Business Loop.



Signed by Marvin E. Myers Date Dec 29, 1993
 Surveyor's Michigan License No. 31600