

**SURVEY & REMONUMENTATION**

APR 27 1995

COMMISSION

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 22, 1994

**LIBER 3 PAGE 155**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>3W</u>	<u>C - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN

COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
30<sup>th</sup> DAY OF Dec, 1994 AT  
4:20 am pm, IN LIBER 3  
PAGE 155.

*Elizabeth W. Wiland*  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on December 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO-A.P. Brewer 1852 Mon-Set Post WIT: 10" S.Pine S79°E 488 lks. 8" S.Pine S78½°W 583 lks.	C.E. Ostling L.1, pg.150 LCRC Mon-Mon. Box (May 17, 1971) WIT: P.Pole N88°10'W 144.0' 10" Oak S70°50'W 104.4'	M.E. Myers Sept. 4, 1991 L.3, pg.43 Mon-Spike WIT: Nail S. side P.Pole N85°W 104.89' Nail N. side 16" Oak S75°W 144.52' PK nail in C pav't N-S N50°W 82.08' C pav't N-S East 66'± Square Iron West 65.86' Fence N-S West 28'±
C.E. Ostling June 1961 Mon-Pav't Box WIT: None	N. Parker Mar. 14, 1979 L.176, pg.168 Mon-Boat Spike MDSH WIT: None	
C.E. Ostling June 17, 1971 L.1, pg.146 LCRC Mon-Mon. Box WIT: P.Pole N88°10'W 144.0' 10" Oak S70°50'W 104.4'		

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Monument - Found 1½" x 15" Spike over 1½" I.D. x 24" Iron Pipe with 1½" x 1½" square head bolt in top  
WIT: Fd. PK nail centerline pav't N-S Rd. N47°W 82.66'  
Fd. nail S. side U.Pole N86°W 105.69'  
Fd. nail NW side 16" R.Oak S74°W 145.25'  
Fd. nail NW side 16" B.Oak S45°W 206.48'  
Fd. 1½" x 1½" sq. head bolt N06°E 17.65'  
Wire fence line N-S West 28.6'±  
Centerline South Bound I-75 S83°E 120'±  
Centerline pav't N-S road N83°W 66.7'±  
Accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon-Set Std. Crawford County Mon. stamped "T26N R3W 31600" in exact location of found iron pipe  
WIT: Fd. PK nail centerline pav't N-S road N47°W 82.66'  
Fd. nail S. side U.Pole N86°W 105.69'  
Fd. nail NW side 16" R.Oak S74°W 145.25'  
Fd. nail NW side 16" B.Oak S45°W 206.48'  
Fd. 1½" x 1½" sq. head bolt N06°E 17.65'  
Set carsonite post S83°E 3.91'  
Wire fence line N-S West 28.6'±  
Centerline South Bound I-75 S83°E 120'±  
Centerline pav't N-S road N83°W 66.7'±



Signed by Marvin E. Myers

Date Dec 29, 1994

Surveyor's Michigan License No. 31600