

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County

LIBER

3 PAGE 270

Located in: Corner Code #

1. Public Land Survey

T26N	R3W	<u>C-13</u>
T25N	R3W	<u>C-1</u>
T	R	
T	R	

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
20 DAY OF Nov, 1997 AT
9:30 am/p.m. IN LIBER 3 OF 44
PAGE 270

Sandra Moore

Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON P. BREWER 1852
SET POST CORNER
WIT ASPEN 6" N33°W 13
PINE 24" N50°E 45

KENNETH J. OSTLING 1975
LEFT 1 1/4" PIPE IN PLACE
FROM PREVIOUS SURVEYS
NO WITNESSES

KENNETH J. OSTLING 1954
FD MSHD PAV'T BOX
NO WITNESSES

NORMAN F. PARKER 1973, LCRC L2, P51
MONUMENT BOX IN BLACKTOP
65.80' WEST OF CENTERLINE OF SOUTH
BOUND 1-75

KENNETH J. OSTLING, 1974
1 1/4 IRON BAR IN PLACE
FROM PREVIOUS SURVEY
NO WITNESSES

MARVIN E. MYERS 31600, 1991, LCRC L3, P38
MON. 1 1/2 SOLID IRON BAR IN MON. BOX
WIT: PK NAIL IN TOP OF GUARD POST NORTH 15.23'
PK NAIL N45°W 31.39'
PK NAIL S50°W
PK NAIL SOUTH 15.65'
WEST END OF BRIDGE DECK EAST 9.90'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2 STEEL ROD IN MONUMENT BOX
PK NAIL IN GUARD RAIL NORTH 15.23'
PK NAIL IN GUARD RAIL N50°W 31.39'
PK NAIL IN GUARD RAIL SOUTH 15.65'
WEST END OF BRIDGE DECK EAST 9.90'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1 1/2" STEEL ROD (LEFT IN PLACE) STAMPED 17614
NAIL & TAG IN GUARD RAIL SOUTH 15.65'
NAIL & TAG IN GUARD RAIL N56°W 31.43'
NAIL & TAG IN GUARD RAIL NORTH 15.27'
CARSONITE POST NORTH 18.43'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Oct 16, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by Larry L. Cavanagh
Surveyor's Michigan License NO. 17614

Date Oct 22, 1997