

CRAWFORD COUNTY REMONUMENTATION STATE OF MICHIGAN  
**LAND CORNER RECORDATION CERTIFICATE** COUNTY OF CRAWFORD  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>26N</u> R <u>3W</u>	D - 5	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

FILED FOR RECORD THIS  
5th DAY OF Jan, 1994 AT  
11:15 am, IN LIBER 3 4/c  
 PAGE 133  
*Elizabeth A. Williams*  
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**LIBER 3 PAGE 133**

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO- 1852 A. Brewer Mon- Post Wit- 10" S. Pine N41°E 13 lks 8" S. Pine S20°W 18 lks June 1961 C.E. Ostling Mon- Pav't box Wit- none given	L192, P327 Oct 1980 N. Parker Mon- 1/2" iron bar in Mon. Box Wit- Not given L157 page 376 Dec 1976 N. Parker ( same as above ) L201 P 157 June 1980 G. Henning Mon- Iron Wit- Not given L4 of Plats page 17 Grayling Industrial Park Mon- Iron in Mon. Box Wit- not given	L315 P 451 Mar 1989 M.E. Myers Mon- Iron in Monument box Wit- not given LCRC L3 Page 44 Mon- Iron in Monument box Wit- Nail & MDOT tag W. side Power Pole S35°E 74.43 PK Nail & MDOT tag in Pavement South 89.32 Nail & MDOT tag NW side service Pole N50°E 87.05 Nail & MDOT tag SW side Guy Pole N40°W 57.65
---	--	--

(See LCRC L.3 P44 for additional corner history)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1/2"x16" pipe in pav't box verified position by measurement to accessories of record and accepted as best available evidence of the position of the the Original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Mon- Set Standard 2"x21" Crawford County Monument  
 Wit- Fd. nail & MDOT tag in West side Power Pole S35°E 74.43  
 FD. PK nail & MDOT tag in Pavement South 89.32  
 Fd. Nail & MDOT tag NW side Service Pole N50°E 87.05  
 Fd. nail & MDOT tag SW side Utility Pole N40°W 57.65



Signed by *Marvin E. Myers* Date Dec 29, 1993

Surveyor's Michigan License No. 31600