

CRAWFORD COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

For corners in

Crawford
 (County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 26N R 3W | D-6 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

FILED FOR RECORDATION
 5th Jan 1994
 11:15 am, IN LIBER 34c
 PAGE 131.
 Register of Deeds
 Register of Deeds Stamp & File Number

LIBER 3 PAGE 131

I, Marvin E. Myers, in a field survey on Dec, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9					11	12			
5												
6	18	●	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set by GLO. June 1980 G. Henning Mon- 5/8" bar WIT_ None given	Corner Set 1961 by C. E. Ostling Mon- 5/8" bar Wit-10" J. Pine N41°W 93.3 18" B. Oak S49°W 37.5 7" Fence Post N79°E 49.8	L168 P 530 June 1970 N. Parker Mon- 5/8" bar Wit- same as Ostling	PLAT OF GRAYLING INDUSTRIAL PARK Richard Mon-5/8" Iron bar
L2 P164 LCRC N. Parker Dec 1977 Mon-5/8" bar Wit- same as Ostling	L3 P45 LCRC Aug 1991 M.E. Myers Mon- Nail over Iron 6" below surface. Wit-Nail in North side Power Pole East 28.79 Nail in NE side of Power pole S25°E 65.85	L195 P325 N. Parker April 1981 Mon- 1/2" bar Wit-Utility pole N75°E 54.0 Utility Pole S25°W 99.3 J. Pine S40°E 68.5	Dec 1977 L165 P401 N. Parker Mon-5/8" bar Wit- Same as Ostlings

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a very rusty 5/8"x15" bar 18" below surface of new asphalt road verified position by measurement to accessories and corners of record and accepted as a careful and faithful establishment of the position for the Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set in exact location Standard Crawford County Monument.
 Wit- Nail in North side of power pole East 28.79
 Nail in NE side of Power Pole S25°E 65.85
 PK nail in West end of South Timber at RR Crossing N10°W 59.54
 Iron South on N-S 1/2 line 123.33
 East edge "35 mph" sign post N22°E 94.65
 N 1/2 corner N01°37'36"E 2643.76
 S 1/2 corner S01°37'52"W 2628.16
 E 1/2 corner N89°35'30"E 2626.37
 W 1/2 corner S89°35'44"W 2621.33



Signed by Marvin E. Myers

Date Dec 21, 1993

Surveyor's Michigan License No. _____