

CRAWFORD COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF CRAWFORD

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>3W</u>	<u>D-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED FOR RECORDING  
 5th Jan 94  
 11:50 AM  
 132  
 3 4c

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**LIBER 3 PAGE 132**

I, Marvin E. Myers, in a field survey on Dec, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7		●										
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- |   |  |   |
|---|--|---|
| GLO - 1852 A. Brewer<br>Mon- Post<br>Wit- 10" S. Pine N41°E 13 lks<br>8" S. Pine S20°W 18 lks             | June 1961 C.E. Ostling<br>Mon- 1½" Pipe<br>Wit- 5" W. Oak S87°E 71.9<br>12" B. Oak N02°W 69.6<br>15" B. Oak N70°W 48.0 | L195 P325 April 1981 N. Parker<br>Mon- ½" bar<br>Wit- P. Pole S86°E 81.8<br>10" W. Oak N5°W 73.0<br>14" B. Oak S7°E 47.0<br>Fence corner N86°W 35.6 |
| LCRC L3, P43 Dec 1991 M.E. Myers<br>Mon- ½" bar<br>( See LCRC L3 P 43 for History<br>and Witness)         | L165 P401 Dec 7, 1977 N. Parker<br>Mon- ½"x24" bar<br>Wit- 8" Oak South 33.7<br>Face of P. Pole E. 82.5                | L206 P 114 Dec 1981 N. Parker<br>Mon- Same as above<br>Wit- same as above   |
| LCRC L. 2 P. 164 Dec 1977 N. Parker<br>Mon- ½" bar<br>Wit- 8" Oak South 33.7<br>Face of P. Pole East 82.5 | L193 P443 Dec 1980 Owen Ayres &<br>Associates Inc. ( Not signed or<br>sealed) Mon- ( refers to L-2 Pl64)               |   |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Intersected witness of record and set standard Crawford County Monument position was accepted as the best available evidence of the position of the Original Corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Mon- Standard 2"x 21" Crawford County Monument.  
 Wit- Nail in W. side 18" Oak S05°E 47.31  
 Nail in North side Power Pole East 81.72  
 Nail in South Side 12" Oak S80°W 67.92  
 Nail in West side 8" J. Pine (record as Oak) N20°W 72.70



Signed by Marvin E. Myers Date dec 29, 1993  
 Surveyor's Michigan License No. 31600