

**SURVEY &
REMONUMENTATION**

APR 27 1995

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Dec 22, 1994

LIBER 3 PAGE 154

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>3W</u>	<u>E - 3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
30th DAY OF Dec, 1994 AT
4:20 am (pm) IN LIBER 3
PAGE 154

Edith W. Land
Register of Deeds, Stamp & File Number

I, Marvin E. Myers in a field survey on December 15, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|--|--|
| GLO-A.P. Brewer 1852
Mon-Set Post
WIT: 10" Tamarack N09°E 6 lks.
8" Spruce S37°W 4 lks. | C.E. Ostling Dec. 18, 1973 L.132, pg.349
Mon-Dept. Cor.
WIT: T.Pole S57°W 36.8'
8" Tamarack S45°E 67.8'
19" W.Pine South 101.0' | N.Parker Dec. 7, 1983 L.220, pg.594
Mon-Conc. Mon. Bronze top
WIT: 16" W.Pine S00°30'E 101.0'
6" Tamarack N44°E 68.47' |
| G. Henning date unknown
Mon-4" Conc. Mon.
WIT: B.T. 16" W.Pine S00°30'E 101.0'
B.T. 6" Tamarack N44°E 67.6' | N. Parker Nov. 4, 1976 L.2, pg. 97
LCRC
Mon-Fd. 4" Conc. Mon. set by
G.D. Henning
WIT: N.B.T. 16" W.Pine S00°30'E 101.0'
N.B.T. 6" Tamarack N44°E 67.6' | G. Boss June 16, 1988 L.280, pg.41
Mon-Fd. Mon. with Bronze Cap
WIT: Spike in 8" Poplar S60°W 42.82
Spike in 4" Poplar N05°W 26.66
Spike in 11" Poplar N80°W 52.5 |
| Ostling Surveys, Inc. Sept. 23, 1968
Mon-Fd. Std. Bronze Marker
WIT: T.Pole S57°W 36.8'
8" Tamarack S45°E 67.8'
19" W.Pine South 101.4' | N. Parker Nov. 5, 1976 L.156, pg.312
Mon-Fd. 4" Conc. Mon.
WIT: 16" W.Pine S00°30'E 101.0'
6" Tamarack N44°E 67.6' | M.E. Myers Sept. 20, 1992
Mon-Fd. Conc. Mon. with Brass Table
of record
WIT: None |
| C.E. Ostling Apr. 23, 1973 L.126, pg.190
Mon-4" Conc. Mon.
WIT: 16" W.Pine S00°30'E 67.6'
6" Tamarack N44°E 67.6' | N. Parker May 15, 1980 L.187, pg.596
Mon-Fd. 4" Conc. Mon.
WIT: 16" W.Pine S00°30'E 101.0'
6" Tamarack N44°E 67.6' | M.E. Myers June 22, 1994
Mon-Fd. Brass Capped Mon. L.2, pg.9
WIT: None |
| | | M.E. Myers
Mon-Conc. Mon.
WIT: 20" W.Pine south 101.4'
10" Tamarack N44°E 67.8'
Spike in SE face 7" Poplar
42.90'
Spike in NE face 4" Poplar
N05°W 26.76' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - Found 1" ID x 25" Iron Pipe with "State of Michigan" Brass Cap over 4" x 48" Conc. Mon. laying on it's side
WIT: Fd. 33" W.Pine S05½°W 100.70'
Fd. nail SE side 9" Poplar S58°W 42.90'
Fd. nail E. side 7" Poplar N01°W 26.76'
Fd. nail S. side 14" Poplar dead & leaning N70°W 52.43'
Fd. 15" Tamarack N50°E 67.40'

Accepted as the best available evidence of the position of the original corner.
C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Std. Crawford County Mon. stamped "T26N R3W E-3 31600 in exact location of iron pipe with Brass Cap
WIT: Fd. 33" W.Pine S05½°W 100.70'
Fd. nail SE side 9" Poplar S58°W 42.90'
Fd. nail E. side 7" Poplar N01°W 26.76'
Fd. nail S. side 14" Poplar dead & leaning N70°W 52.43'
Set wit. tag & nail E. side 3" R.Oak S06°W 78.72'
Set wit. tag & nail NW side 15" Tamarack N50°E 67.88'
Set carsonite post West 3.20'



Signed by Marvin E. Myers Date Dec 29, 1994
Surveyor's Michigan License No. 31600