

APR 27 1995

COMMISSION

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE 12-29-94

LIBER 3 PAGE 168

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> , R <u>3W</u>	<u>E-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
30th DAY OF Dec, 1994 AT
4:20 am/pm, IN LIBER 3
PAGE 168.

Elizabeth W. Williams
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin E. Myers, in a field survey on Dec 19, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-A. P. Brewer 1852 Mon- Set Post Wit- 10" Cedar N30°W 9 lks 13" Tamarack S32°E 12 lks	L167, P470 N. Parker 4-4-1978 Mon- ½" bar Wit-found old BT 10" Cedar stump NW 5.8	M. E. Myers June 1994 Mon- Found ½" bar 0.8 above surface Wit- Found G. D. Henning Nail and tag in SE face 5" Cedar N51°W 12.95
G. Henning date unknown Mon- found Original Post Wit- none given	NBT 12" Cedar NNW 12.7 NBT 8" Cedar SW 16.7	Found G.D. Henning Nail & tag N. face 8" Cedar S22°W 15.68
C.E. Ostling LCRC 12-14-1971 Mon- Found ½" bar Wit- 16" Cedar N40°E 22.9 8" Cedar S20°W 15.8 5" Cedar N45°W 12.65	L181, P570 N. Parker 9-7-1979 Mon & Wit same as above L184, P261 N. Parker 12-5-1979 Mon & Wit same as above	Set nail S. side 4" Cedar N88°E 17.54 Set nail S. side 5" Cedar S72°W 20.50

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" x 48" Iron Bar; found GDH wit tag SE face 5" Cedar N48½°W 12.95; found "GDH" wit tag N. face 9" Cedar S24°W 15.81; foud nail S. side 5" Cedar N90°E 17.54; found nail S. side 5" Cedar S79°W 20.48; found blaze S. face 5" Cedar N05°E 19.90; found 10" Cedar stump NW 5.8'±
Accepted as a perpetuation of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-Set standard Crawford County Monument marked cap "31600, T26N, R3W, E-4" in exact location of found ½" bar.
Wit- Set carsonite post S03°W 4.47
Found nail S. side 4" Cedar N90°E 17.54
Found nail S. side 5" Cedar S72°W 19.90
Found G. D. Henning nail & tag N. face 9" Cedar S24°W 15.81



Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Dec 29, 1994