

**SURVEY &  
REMONUMENTATION**

APR 27 1995

COMMISSION

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 22, 1994

**LIBER 3 PAGE 159**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> , R <u>3W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
30<sup>th</sup> DAY OF Dec., 1994 AT  
4:20 am (pm) IN LIBER 3  
PAGE 159.

*Elizabeth W. Land*  
**Register of Deeds Stamp & File Number**  
Register of Deeds

I, Marvin E. Myers, in a field survey on Dec 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- |   |   |
|---|---|
| GLO-A. P. Brewer 1852<br>Mon- Set Post<br>Wit- 6" Cedar N51°W 33 lks<br>7" Cedar S34°E 25 lks.  | L271, P567 N. Parker 10-27-84<br>Mon- 1/2" iron bar in pav't<br>Wit- none<br>LCRC L.3, P44 M.E. Myers 9-16-91<br>Mon- 1" iron<br>Wit- PK nail top of Guard post N60°W 68.84<br>Nail in SW side 18" Pine S50E 78.60<br>PK nail top of Guard Post S75°W 93.79<br>nail SW side 12" Poplar N30°E 57.17<br>Center line of Creek West 147'± |
| G. Henning (date unknown)<br>Mon- Iron in Pav't<br>Wit- Old Fence line North<br>C.E. Ostling June 1961<br>Mon- Pav't Box<br>Wit- none<br>C.E. Ostling 12-03-1971<br>Mon- Found 1/2" bar<br>Wit- 16" Cedar S46°W 51.35<br>26" Tamarack S43°E 117.4 |   |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 3/4" x 18" iron pipe with nail & washer in top in Mon Box 1.3± N of Center of M-72; found PK nail top center of E. Guard rail post N60°W 68.69; found PK nail top center of E. Guard Rail Post S73°W 93.78; found 13" dead Poplar N49°E 61.45 to face; found blaze N. face 14" Cedar S26°W 51.28.  
Accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Mon-Set standard Crawford County Monument marked cap "31600" in monument box.  
Wit- Found PK nail top center E. Guard rail post N60°W 68.69  
Found PK nail top Center E. Guard rail post S73°W 93.78  
Set nail & tag SE side 9" W. Pine N47°E 68.20  
Set nail & tag W. side 8" Cedar S09°E 52.15  
Set carsonite post S06°W 42.02



Signed by Marvin E. Myers

Date Dec 29, 1994

Surveyor's Michigan License No. 31600