

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich P.A. 1970

For corners in
 Crawford County

LIBER

3 PAGE 272

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

Located in: _____ Corner Code # _____

1. Public Land Survey

T26N	R3W	E-13
T25N	R3W	E-1
T	R	
T	R	

FILED FOR RECORD THIS
20 DAY OF Nov., 1997 AT
9:30 am/pm, IN LIBER 3 OF LC
 PAGE 272

Sandra Moore
 Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON B. BREWER 1852
 PINE 10 N75 1/2 W 20
 DO 8 N35E 58
 CARL E. SHANGRAW 25872, 1990
 WIT: PK IN NW SIDE 10" J. PINE S30°W 64.48'
 PK IN S SIDE C.P. POLE N75°W 99.53'
 NAIL IN SW SIDE 14" OAK N65°W 78.10'
 NAIL IN W SIDE 8" J. PINE N15°E 50.52'

KENNETH J. OSTLING 10068
 LCRC L1 P 163 1971
 SET 1" X 24" PIPE
 16" OAK S20°W 93.4'
 14" OAK N57°W 77.5'
 5" J. PINE N4°W 49.8'
 JAMES L. SCHWANDT 26466
 FD 1 1/4" PIPE
 SET TAG 8" J PINE 64.31 S15°W
 FD SPK DNR POST N05°E 32.88'
 FD TAG 4" J. PINE N05°W 49.78'
 FD SPK 12" OAK N45°W 78.0'

OWEN AYRES & ASSOC., INC.
 L 185 P 612 1980
 FD 1 1/4" PIPE IN PAVT
 S35°W N & T IN 9" JACK PINE 64.42'
 N50°W N & T IN 14" OAK 78.08'
 N 4°E N & T IN DNR WITNESS POST 32.89'
 MARVIN E. MYERS 31600 LCRC L3 P 38 1991
 1 1/2 PIPE
 WIT: PK IN W. FACE 12" PINE S25°W 64.50'
 NAIL IN W. FACE 12" PINE 63.73
 NAIL IN E. FACE 14" OAK N60°W 77.55'
 NAIL & RLS TAG #26446 E FACE PINE N05°W

OWEN AYRES & ASSOC., INC.
 L 218 P 400 1983
 FD 1 1/4" PIPE IN PAVT
 S 35°W 64.42' N & T IN 6" JACK PINE
 N50°W 78.08' N & T IN 14" OAK
 N04°E 32.89' N & T IN DNR WITNESS POST

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

MARVIN E. MYERS 31600
 FD 1 1/2" PIPE
 PK IN W SIDE 12" PINE S25°W 64.50
 NAIL IN W SIDE 12" PINE N40°E 53.73'
 NAIL IN E SIDE 14" OAK N60°W 77.55'
 NAIL & LS TAG #26446 IN E SIDE 6" PINE
 NW 49.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1" X 24" PIPE OVER LARGE IRON OBJECT, POSSIBLY A PIPE, COULD NOT REMOVE
 PK IN W SIDE OF 12" PINE S25°W 64.50'
 NAIL IN E SIDE 14" OAK N60°W 77.55'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CRAWFORD COUNTY MONUMENT STAMPED 17614, 1997
 NAIL & TAG IN 18" B OAK N60°W 77.45'
 NAIL & TAG IN 12" J. PINE S25°W 64.23'
 *NAIL & TAG IN 13" SCOTCH PINE N45°E 63.55'
 *NAIL & TAG IN 6" CHERRY S10°E 78.0'
 CARSONITE POST NORTH 31.8'

*NEW WITNESSES

**CRAWFORD COUNTY
 PEER GROUP APPROVAL
 DATE Oct 16, 1997**

Marvin E. Myers P.E.M.
 Marvin E. Myers, P.S.
 County Surveyor

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *Larry L. Cavanagh*
 Surveyor's Michigan License NO. 17614

Date Oct. 22, 1997