

MAR 27 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Table with columns: For corners in Crawford (County), Located In: (Town, Range, Section), Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

27 DEC 95 3:00 P.M.

SANDRA MOORE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Marvin E. Myers, in a field survey on, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column G and row 2.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-James Mullett 1839 Mon.-Set Post WIT: 9" Cedar S89°E 14 lks. 11" Cedar S62°W 15 lks.
N. Parker June 1972 L.2, pg.91 Mon.-1/2"x24" Bar set WIT: NBT 10" Cedar South 9.00' NBT 12" Cedar East 9.00'
G. Boss June 1988 L.280, pg.41 Mon.-Set 1/2"x30" Iron with Brass Cap (next to 3" sq. Cedar Post) WIT: 14" Cedar N80°E 8.97' 12" Cedar South 9.03' 7" Cedar N10°E 8.40' 12" Cedar West 11.15'

LIBER 3 PAGE 224-B

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monument - 1/2" x 36" Bar & Cap #17022 0.25' South of 3' x 3" x 59" Original Cedar Post
WIT: Nail SE side 7" Cedar N35°E 8.20'
Nail South side 13" Cedar (dead) with Blaze & Scribe on West face S80°E 9.03'
Nail South side 11" Cedar N60°W 11.00'
Nail West side 14" Cedar S10°W 9.25'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Dec 19, 1995

Signature of Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon.-Set standard Crawford County mon. stamped "G-2 T26N, R3W 1995 #31600"
WIT: Set Carsonite Post East 3.00'
Nail SE side 7" Cedar N35°E 8.20'
Nail S. side 13" Cedar (dead) with Blaze & Scribe on W. face S80°E 9.03'
Nail S. side 11" Cedar N60°W 11.00'
Nail W. side 14" Cedar S10°W 9.25'



Signed by Marvin E. Myers

Date Dec 21, 1995

Surveyor's Michigan License No. 31600