

**SURVEY & REMONUMENTATION**

**APR 07 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich P.A. 1970

**SECTION**

**LIBER**

**3 PAGE 274**

For corners in  
Crawford County

Located in: Corner Code #

I. Public Land Survey

T26N	R 3W	G-13
T25N	R 3W	G-1
T	R	
T	R	

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

FILED FOR RECORD THIS  
20 DAY OF NOV, 1997 AT  
9:30 am, IN LIBER 30 OF LC  
PAGE 274.

*Sandra Moore*  
Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**A. Description of original monument and accessories and/or subsequent restoration:**

ADDISON P. BREWER 1954 A CEDAR 12 FOR CORNER NO WITNESSES	KENNETH J. OSTLING 10068 1974 LCRC 1" PIPE CENTERLINE 4 MILE RD REWITNESS 5" R. PINE S9°W 95.5' FACE OF P. POLE S43°E 51.5' FACE OF GUY POLE N51°E 49.25'
KENNETH J. OSTLING 10068 1854 DNR SURVEY FD PIPE PREVIOUS SURVEY NO WITNESSES	OWEN AYRES & ASSOC., INC. 1980 L185 P614 FD 1 1/4" PIPE UNDER PAVT N45°E NAIL & TAG IN GUY POLE 49.54' N45°W CENTERLINE 3" WELL CASING 52.03' S50°W NAIL & TAG IN P.P. 51.81' ON CENTERLINE ROAD EAST AND WEST
KENNETH OSTLING 10068 1971 LCRC L1 P162 FD 1/2 BAR REPLACE WITH 1"X 2' PIPE 10" OAK N56°W 66.9' 2" PIPE N35°W 52.0' 12" J. PINE N14°E 55.1'	OWEN AYRES & ASSOC., INC. 1983 L215 P400 FD 1 1/4" PIPE UNDER PAVT SAME WITNESSES AS ABOVE

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FD 1" PIPE 28" LONG WITH 1/2 BAR IN BOTTOM  
N45°E NAIL & TAG IN GUY PPOLE 49.54'  
N45°W 52.03' CENTERLINE 3" WELL CASING  
S50°E 51.81' NAIL & TAG IN POWER POLE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET CRAWFORD COUNTY MONUMENT STAMPED 17614, 1997  
\*NAIL & TAG IN P. POLE S40°W 48.35'  
NAIL & TAG IN P. POLE S50°E 51.78'  
NAIL & TAG IN GUY POLE N45°E 49.58'  
NAIL & TAG IN CENTER OF 3" WELL CASING N36°W 52.05'  
CARSONITE POST N5°E 35.4'

\*NEW WITNESSES

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Oct 16, 1997**

*Marvin E. Myers*  
**Marvin E. Myers, P.S.  
County Surveyor**



Signed by *Larry L. Cavanagh* Date *Oct. 22, 1997*  
Surveyor's Michigan License NO. 17614