

**SURVEY & REMONUMENTATION**

MAY 05 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code <u>H-3</u> ✓
1. Public Land Survey	T <u>26N</u> R <u>3W</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
CRAWFORD COUNTY  
RECORDED

7 JUN 96 9:48 A.M.

SANDRA MOORE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**LIBER 3 PAGE 235**

I, Marvin E. Myers, in a field survey on Dec 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO- James Mullett 1839 Mon - Set Post Wit - 10" S. Pine N87½°E 29 Lks. 12" S. Pine S5°E 20 Lks.	C. Eugene Ostling Feb 1964 Mon - Found Concrete Mon. Wit - 12" J. Pine S50°W 18.0 24" Norway Pine N27°E 106.3
G. D. Henning Nov 1956 Mon - Found 3" Pipe Wit - BT 12" J. Pine S50°W 18.00 BT 24" Norway N27°E 106.3	Gary Boss June 1988 Mon - Found ½" Iron rod in concrete Wit - 11" J. Pine N25°W 49.33 12" J. Pine N60°E 65.96 12" Oak South 37.83

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 5" concrete tile monument with ½" bar inside  
WIT: 30" Norway N26°E 106.35'  
17" J. Pine S44°W 18.20'  
13" B. Oak S05°W 37.79' Nail in E. side  
13" J. Pine N21°W 49.35' Boss nail & tag in SW side  
13" J. Pine N59°E 65.95' Boss nail & tag in NW side  
8" J. Pine N09°E 14.72'

**CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Dec 19 1995**

*Marvin E. Myers*  
**Marvin E. Myers, P.S.  
County Surveyor**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monument - Set standard Crawford County Mon. stamped "MEM 31600"  
WIT: Set carsonite post West 0.58'  
13" B. Oak S05°W 37.79' Nail in E. side  
13" J. Pine N21°W 49.35' Boss nail & tag in SW side  
13" J. Pine N59°E 65.95' Boss nail & tag in NW side



Signed by *Marvin E. Myers* Date DEC 27 1995  
Surveyor's Michigan License No. 31600