

SURVEY & REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich P.A. 1970

For corners in **SECTION LIBER**
 Crawford County

3 PAGE 275

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

1. Public Land Survey

Located in: T26N R3W Corner Code # H-13
T25N R3W H-1
T R
T R

FILED FOR RECORD THIS
20 DAY OF NOV, 1997 AT
9:30 am, IN LIBER 3 OF LC
 PAGE 275
Sandra Moore
 Register of Deeds

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON P. BREWER 1852
 SET POST
 PINE 8 N45W 12
 PINE 6 N50E 38

JOHN I NELSON 21273
 L204 P 131 1982
 FD 3/8" RE-ROD IN CENTERLINE OF ROAD
 SET SPIKE IN NW SIDE OF 10" J. PINE AZ 62° 76.86'
 SET SPIKE IN EAST SIDE OF P. POLE AZ 150° 41.34'
 SET SPIKE IN NW SIDE OF 8" OAK AZ 238° 88.65'
 SET SPIKE IN E SIDE OF 30" OAK AZ 351° 115.44'

NORMAN F. PARKER 16939
 LCRC L2 P90 1976
 FD 1/2" BAR IN RD
 OLD B.T. J. PINE N30°W 51.5'
 OLD B.T. J. PINE N40°E 48.0'
 B.T. 8" J. PINE N40°E 76.0'
 B.T. 10" J. PINE N14°W 48.4'

JOHN I NELSON 21273
 LCRC L2 P248 1982
 FD 3/8" RE ROD
 SET SPIKE IN NW SIDE OF 10" J. PINE AZ 62° 76.86'
 SET SPIKE IN EAST SIDE OF P. POLE AZ 150° 41.34'
 SET SPIKE IN NW OF 8" OAK AZ 238° 88.65'
 SET SPIKE IN EAST SIDE OF 30" OAK AZ 351° 115.44'

NORMAN F. PARKER 16939
 L162 P399 1977
 OLD J. PINE N30°W 51.5'
 OLD J. PINE N40°E 48.0'
 8" J. PINE N40°E 76.0'
 10" J. PINE N14°W 48.4'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1/2" X 18" STEEL BAR OVER 1/2" BAR IN 1 1/4" PIPE (PIPE LEFT UNDER MONUMENT)
 SPIKE IN NW SIDE OF 10" J. PINE AZ 62° 76.86'
 SPIKE IN EAST SIDE OF P. POLE AZ 150° 41.34'
 SIDE SPIKE IN NW OF 8" OAK AZ 238° 88.65'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CRAWFORD COUNTY MONUMENT STAMPED 17614 1997
 NAIL & TAG IN 12" B. OAK S55°W 88.51'
 NAIL & TAG IN 14" J. PINE N59°E 76.79'
 NAIL & TAG IN 8" J. PINE N30°W 104.02'
 NAIL & TAG IN P. POLE S25°E 41.15'
 CARSONITE POST SOUTH 33.5'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

CRAWFORD COUNTY
PEER GROUP APPROVAL
 DATE OCT 16, 1997

Marvin E. Myers
Marvin E. Myers, P.S.
 County Surveyor

Signed by Larry L. Cavanagh
 Surveyor's Michigan License NO. 17614

Date Oct. 22, 1997

