

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION
Crawford
(County)

Located In:

Corner Code #

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED

7 JUN 96 9:48 A.M.

SANDRA MOORE
REGISTER OF DEEDS

1. Public Land Survey	T	26N	R	3W	I - 2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 3 PAGE 238

I, Marvin E. Myers, in a field survey on December 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO -James Mullett 1839
Mon.-Set Post
WIT: 10" S.Pine N44°E 7 lks.
6" S.Pine S68°W 35 lks.

N. Parker 1972 L.1, pg.132
Mon.-½" Bar (from wit. in field survey by G. Ostling 1964)
WIT: 12" J.Pine N36°E 118.80'
6" J.Pine S78°E 72.00'

N. Parker July 1986 L.247, pg.13
Mon.-½" Bar in road
WIT: 14" J.Pine N36°E 118.80'
8" J.Pine S78°E 72.00'
Face U.P. S85°W 34.50'

G. Eugene Ostling Feb. 1964
Mon.-8" Spike
WIT: 12" J.Pine N36°E 118.80'
6" J.Pine S78°E 72.00'

N. Parker 1982 L.206, pg.112
Mon.-½" Bar
WIT: 12" J.Pine N36°E 118.80'
6" J.Pine S78°E 72.00'
Face U.P. S85°W 34.50'

G. Boss June 1988 L.260, pg.41
Mon.-Fd. 5/8" Bar in G road
WIT: Spike in U.P. S85°W 34.81'
7" J.Pine S45°W 81.84'
5" J.Pine S80°E 38.13'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Monument - Found ½"x18" bar over ½"x14" iron bar in mon. box 1' W. of centerline Headquarters Rd.
Found Boss nail & tag in Northeast side of 9" J. Pine S48°W 81.88'
Found Boss nail & tag in North side of utility pole S87°W 34.82'
Found Boss nail & tag in North side of 7" J.Pine S61°E 38.10'
Found nail in Northwest side of 4" J.Pine N71°E 42.96'
Centerline North - South road 1' East

**CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Dec 17, 1996**

Marvin E. Myers
**Marvin E. Myers, P.S.
County Surveyor**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Set Standard Crawford County Mon. stamped (I-2 T26N, R3W 31600" in mon. box 1' West of centerline Headquarter Road
WIT: Boss nail & tag SE side 9" J.Pine S48°W 81.88'
Boss nail & tag N. side U.P. S87°W 34.82'
Boss nail & tag N. side 7" J.Pine S61°E 38.10'
Nail NW side 4" J.Pine N71°E 42.96'



Signed by *Marvin E. Myers*

Date *May 21, 1996*

Surveyor's Michigan License No. 31600