

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Crawford County

**LIBER 3 PAGE 276**

STATE OF MICHIGAN  
COUNTY OF CRAWFORD

1. Public Land Survey

Located in:

Corner Code #

T26N R 3W  
T25N R 3W  
T R  
T R

I-13  
I-1

FILED FOR RECORD THIS  
30 DAY OF NOV, 1997 AT  
9:30 am/pm, IN LIBER 3 OF LC  
PAGE 276

*Sandra Moore*

Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON P. BREWER  
SET POST  
PINE N80°W 22  
PINE N34°E 20

KENNETH J. OSTLING 1954  
FD PIPE BY PREVIOUS SURVEY  
NO WITNESSES

NORMAN F. PARKER 16939  
L139 P480 1974  
FD 1/2 IRON BAR

N88°W 79.9 10" J. PINE  
N45°E 91.8' 6" J. PINE  
N54°W 65.5' 10" J. PINE  
S44°W 47.7' 5" J. PINE

NORMAN F. PARKER 16939  
L2 P90 1976  
FD 1/2" BAR IN RD  
OLD BT J. PINE STUMP N40°W 48.4'  
OLD BT 6" J. PINE N45°E 91.8'  
1/2 BAR NORTH 33.0'

NORMAN F. PARKER 16939  
L162 P399 1977  
OLD J. PINE STUMP N40°W 48.4'  
OLD 6" J. PINE N45°E 91.8'

GEORGE D. HENNING 2240  
L180 P513 1979  
FD 1/2" BAR  
10" J. PINE N32°W 79.9'  
6" J. PINE N43°E 91.8'  
10" J. PINE S36°W 63.2'  
5" J. PINE S44°30'E 90.7'

JOHN I NELSON 21273  
L2 P246 1982

SET NAIL W/RLS TAG 21273 IN WEST SIDE OF P. POLE AZ 22° 36.88'  
SET NAIL W/RLS TAG 21273 IN NE SIDE OF 6" OAK AZ 157° 44.32'  
SET NAIL W/RLS TAG 21273 IN NW SIDE OF 8" OAK AZ 230° 125.20'  
SET NAIL W/RLS TAG 21273 IN EAST SIDE OF 6" OAK AZ 355° 108.88'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1/2" X18" STEEL BAR OVER 1" PIPE  
NAIL W/RLS TAG 21273 IN WEST SIDE OF P. POLE AZ 22° 36.89'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


SET CRAWFORD COUNTY MONUMENT STAMPED 17614 1997  
\*NAIL & TAG IN 10" J. PINE N43°E 91.95'  
NAIL & TAG IN P. POLE N19°E 36.87'  
\*NAIL & TAG IN 7" J. PINE N23°W 58.70'  
\*NAIL & TAG IN 14" J. PINE S28°W 98.66'  
NAIL & TAG IN 10" N. PINE S65°E 89.45'  
CARSONITE POST N40°E 44.25'

\*NEW WITNESSES

**CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE OCT 16, 1997**

*Marvin E. Myers*  
**Marvin E. Myers, P.S.  
County Surveyor**

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License NO. 17614

Date Oct. 22, 1997