

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich P.A. 1970

For corners in
 Crawford County

LIBER

3 PAGE 280

STATE OF MICHIGAN
 COUNTY OF CRAWFORD

Located in:

Corner Code #

1. Public Land Survey

T26N R 3W
 T25N R 3W
 T25N R 2W
 T26N R 2W

M-13 ✓
 M-1 ✓
 A-1 ✓
 A-13 ✓

FILED FOR RECORD THIS
20 DAY OF Nov, 1997 AT
9:30 am/pm, IN LIBER 30 ELC
 PAGE 280

Sandra Moore

Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey September, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

SET ADDISON P. BREWER
 SET POST
 PINE 10 N30 1/2W 11
 PINE 8 S48W 15

KENNETH J. OSTLING 10068 1979
 FD 1/2" IRON BAR AT CORNER
 BY HENNING, 1937
 NO WITNESSES

JK

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1/2" BAR AND THE REMAINS OF AN OLD WOOD POST

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CRAWFORD COUNTY MONUMENT STAMPED 17614 1997
 NAIL & TAG IN 7" J. PINE N29°W 66.93'
 NAIL & TAG IN 9" J. PINE N26°E 30.15'
 NAIL & TAG IN 8" J. PINE S13°E 41.03'
 NAIL & TAG IN 9" J. PINE S55°W 32.16'
 CARSONITE POST S12°W 21.10'

THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**CRAWFORD COUNTY
 PEER GROUP APPROVAL**

DATE OCT 16, 1997

Marvin E. Myers, P.S.

Marvin E. Myers, P.S.
 County Surveyor



Signed by *Larry Cavanagh*
 Surveyor's Michigan License NO. 17614

Date Oct 22, 1997