

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.26 NR.3.W

Crawford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 28 and 33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

8" W. Oak - S13W - 18 1/2 links

7" R. Oak - East - 52 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while completing a partial resurvey of this township. Set corner from probable SW government BT-- the one nearest to conformity to a proportionate corner. Could find no trace of post because of dry soil, but this position checks acceptably with point for proportioned corner.

Corner was placed and witnessed July 16, 1959.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 7/29/59