

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 3. W.

----- Grandford ----- COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 14 & 23 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER -----

10" Red Oak - N 40 W - 62 Links -----

8" Red Oak - S 90 E - 43 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew, while making a partial resurvey of this Township. One original R.T. still in place, cut off below stump height. Found remains of two stakes in place, at corner.

Corner was placed and witnessed November 6, 1953.

SURVEYORS SEAL

SIGNED *John C. [Signature]* DATE 1/27/54
REGISTERED LAND SURVEYOR