

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 3. W. . .

Crawford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 15 and 22 . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" J. Pine - S15E - 26 1/2 links
7" J. Pine - S70W - 48 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division Surveyor while completing a partial retracement of this township. Set corner mid-point, on line between section corners. Could not identify government BTs. Old NBTs appear to face a fence corner which is about 10' NE of our point, but can find no support for this position considering the section corners east and west. An old stake, also, about 2' south of our corner.

Corner was placed and witnessed August 5, 1959.

SURVEYORS SEAL

SIGNED

Harold J. O'Neil
REGISTERED LAND SURVEYOR

DATE 8/6/59