

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 3 W.

Crawford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 23 and 24

DESCRIPTION OF CORNER MONUMENT 1" x 24" pipe

WITNESSES TO CORNER

7" J. Pine - S2E - 60 links

10" J. Pine - S89W - 14 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established at midpoint, on line, between Section corners, by Forestry Division Land Surveyor while completing a partial retracement of this township. Good corners north and south, but could not identify anything for government BTs. A 1/4" iron rod is about 6" SW from our point, but can find no support for that position.

Corner was placed and witnessed August 5, 1959.

SURVEYORS SEAL

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE

8/6/59