


# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 26 N. R. 3 W. 	C-11; C-12; G-13
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 28, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11 Restored corner as identified in 1953 survey, which was probably by G. F. DeLaMater. Set corner 204.6' south of monument box which appears to be erroneously considered as the corner.
- C-12 Set by proportionate measurement, MPOL, between section corners.
- G-13 Previous corner rewitnessed, both NBT's dead.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11	C-12	G-13
DNR monument	DNR monument	1" pipe $\zeta$ 4 Mile Road
12" W. Oak N84°W 52.6	12" Bl. Oak West 84.7	rewitness
7" Maple S33°W 81.0	8" W. Oak S47°W 92.6	5" R. Pine S09°W 95.5
5/8" rod North 204.6		face of P. pole S43°E 51.5
ROW fence West 27		face of guy pole N51°E 49.25

SIGNED BY Kenneth J. Ostling DATE \_\_\_\_\_  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)