

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 3 W.	I-10; J-9; J-10; K-10
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 12, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. ~~Description of original monument and accessories and/or subsequent restorations.~~
C. (continued)

K-10			
Set DNR Mon. in Place of Spike			
5" J. Pine	N80°W	33.55	
10" W. Oak	N25°W	44.4	
Cedar Post	West	14.0	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-10 Set by Forestry Div. survey crew in 1954; mon. replaced in 1971 & rewitnessed.
- J-9 Corner established in 1954 survey by DNR during retracement in this township.
- J-10 Set corner at calculated intersection of true ¼ lines.
- K-10 Found spike at MPOL between section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10	J-9	J-10
DNR Mon. & cedar post	Fd. DNR mon. set red-top post	5/8x40" Iron Bar w/Cap
7" W. Oak S53°E 22.25	*6" J. Pine N81°E 10.7	5" Oak N03°E 4.95
8" Maple S13°W 36.0	*6" J. Pine N25°W 18.65	6" Oak N54°W 11.0
18" W. Oak N47°W 33.15	*1954 witnesses	


SIGNED BY Kenneth J. Ostling DATE 11-15-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY