

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.26 NR. 3 W.

Crawford

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 23 and 26

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

4" J. Pine - N76E - 16 links

4" J. Pine - N30W - 28½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint, on line between section corners, by Forestry Division Land Surveyor while making a partial retracement of this township. Could locate nothing definite for gov't BTs.

Corner was placed and witnessed August 5, 1959.

SURVEYORS SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 8/6/59