

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 3 W.	(I-11) J-11; (K-9) K-11
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 12, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~
 C. (continued)

K-11
 Found railroad rail
 RLS Cap (16939) in face of PP
 N41°W 41.4
 PK in face of PP
 N50°E 42.68


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-11 Corner previously established in 1954 survey project by this Department.
- J-11 Found railroad rail at corner, nearly at MPOL, probably as established in early survey by Newman. Best evidence of corner.
- K-9 Found 1" pipe set by survey crew in 1954, replaced w/DNR mon. red-top post 6'W. Corner is on W side of road.
- K-11 Corner in Q of roads N-E-W, as previously established by unknown, but probably Newman in early county survey. Used in other surveys in this area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11	J-11	K-9
Found DNR Monument	Left RR rail in place	Fd. 1" Pipe; Set DNR Monument
7" W. Oak N07°E 25.9	6" W. Oak N08°W 8.85	*8" J. Pine S73°E 22.8
18" R. Pine N75°W 21.65	20" Oak N50°E 22.1	*7" J. Pine (tree cut)
*10" J. Pine S49°W 10.9	Set cedar post 10' North	N35°W 9.85
*1954 Witnesses		6" J. Pine S31°W 30.15
		*1954 Witness

SIGNED BY Kenneth J. Ostling DATE 11-15-78
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY