

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 26 N. R. 3 W.	H-4; I-6; H-5
2. PROPERTY CONTROLLING IN SECTION 15 _____	T. 26 N. R. 3 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 6, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. Continued:

	H-5			I	
Set 4" nail in M-72				Set 4" nail in M-72	
10" Jack Pine	40.5'	S-19°E		7" Red Pine	37.1' S-20°E
12" Jack Pine	63.8'	S-43°W		8" Red Pine	40.0' S-19°W

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- H-4 Set corner at computed position for center of section using Henning 1956 survey data, and subsequent local surveys.
- I-6 Set corner by proportionate measurement between section corners, as was used in surveys in adjacent sections.
- H-5 Set corner at midpoint on line between section corners, said point being used in 1956 Henning survey and other subsequent surveys.
- 1 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	H-4			I-6	
5/8" rod w/cap				Set DNR mon.	
8" Jack Pine	13.2'	S-74°W		6" Jack Pine	10.4' N-32°E
8" Jack Pine	23.8'	N-67°W		6" Jack Pine	16.6' S-58°E

SIGNED BY: Kenneth Ostling
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE: 3-12-81



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CRAWFORD COUNTY