

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 26 N. R. 3 W.	K-9; L-7; K-7; M-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl R. Johnson, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 11, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. Continued:

~~As described in original record and as shown on attached exhibits~~

<u>K-7</u>	<u>M-11</u>
Fd DNR mon & set cedar post	Set DNR mon at fd 1" pipe
*12" Jack Pine S67°E 28.9'	Power Pole N22°W 56.9'
6" Jack Pine S30°W 15.6'	½" Sq. Bolt N16°E 23.6'
5" Red Oak N60°W 18.1'	8" Red Oak S42°E 64.8'

\* 1954 DNR Survey


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 K-9 - Set at the location as previously established in DNR survey (1978). Re-witnessed by County Road Commission (1983).  
 L-7 - Set at found ½" re-rod from unknown origin. No other conclusive evidence of corner.  
 K-7 - Corner previously established in DNR survey (1953).  
 M-11 - Found 1" pipe as used in previous surveys in area by local surveyors.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>K-9</u>	<u>L-7</u>
Set DNR monument	Set DNR mon & cedar post
30" Red Oak N55°W 61.4'	6" Black Oak N64°W 13.5'
9" Red Oak S41°W 78.3'	5" White Pine N38°E 29.0'
Cedar Post w/tag N86°W 40.0'	

SIGNED BY *Carl R. Johnson* DATE 4/3/85

SURVEYOR'S MICHIGAN REGISTRATION NO. 30083



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CRAWFORD COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET