

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich P.A. 1970

For corners in
Crawford County

LIBER

4

PAGE

36

Located in:

Corner Code #

1. Public Land Survey

T26N	R4W	E-3
_____	_____	_____
T_____	R_____	_____
_____	_____	_____
T_____	R_____	_____
_____	_____	_____

STATE OF MICHIGAN
COUNTY OF CRAWFORD

FILED FOR RECORD THIS
29th DAY OF Sept. 19 99 AT
9:00 am, IN LIBER 4
PAGE 36

Sandra Moore.
Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey August, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON BREWER GLO 1852
SET POST
S. PINE 7° N60°W 25 LKS
S. PINE 10° S38°E 88 LKS

5TH ADDITION TO PORTAGE
LAKE PARK 1902
LI, PG 24
WILLIAM BLENSHAW, SURVEYOR
1/4 POST
NO WITNESSES

G.F. DELAMATER 1942
BOOK 3, PG 31 CC RECORDS
1 1/4 PIPE IN COR (SET FROM ORIG. BT'S)
B. OAK 6° N50°E 53.1'
Y. PINE 8° S50°E 103.4'
S. PINE 7° S42°W 86.1'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" PIPE WITH CONSERVATION CAP (2' BELOW SURFACE) 11.5' EAST OF CENTERLINE OF MCINTYRE LANDING RD.
AND 5' NORTH OF PORTAGE HTS AVE. (WEST)
NE WIT (NOW 13" B. OAK 63.18')
SE WIT (NOW 15" N. PINE 103.59')

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LEFT 1 1/4" PIPE/MICH DEPT OF CONSERVATION CAP IN PLACE, SET STD CRAWFORD COUNTY MONUMENT OVER IT
WIT: NAIL & TAG IN 14" J. PINE N45°W 91.29'
NAIL & TAG IN 13" B. OAK (1942) N50°E 63.18'
NAIL & TAG IN 15" NORWAY (1942) S50°E 103.59'
NAIL & TAG IN POWER POLE S45°W 58.18'
CARSONITE POST EAST 16.4'

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Sept 10, 1999

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor



Signed by *Larry L. Cavanagh* Date Sept. 14, 1999
Surveyor's Michigan License NO. 17614