

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich P.A. 1970

For corners in  
Crawford County

**LIBER**

**4**

**PAGE**

**35**

Located in: Corner Code #

1. Public Land Survey

T26N	R 4W	F-3
T	R	
T	R	
T	R	

STATE OF MICHIGAN

COUNTY OF CRAWFORD

FILED FOR RECORD THIS:

2:45 DAY OF Sept 19 99 AT 9:00 am/pm IN LIBER 4 LC

PAGE 35

*Sandra Morris*  
Register of Deeds

Register of Deeds Stamp & File Number

I, Larry L. Cavanagh, in a field survey August, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

ADDISON BREWER GLO 1852	M. MYERS, PS 1997
SET POST	AMENDED PLAT L4, PG 35
Y. PINE 22° N22°W 34 LKS	REFERENCES, BUCKLER'S LCRC (1956)
Y. PINE 20° S18°E 34 LKS	

5TH ADDITION TO PORTAGE  
LAKE PARK 1902  
L1, PG 24  
WILLIAM BLENshaw, SURVEYOR  
1/4 POST  
NO WITNESSES

LCRC L5, P95 1956  
BILLY D. BUCKLER, RLS  
FD HOUGHTON TILE, SET  
FROM GLO WIT.  
1" PIPE/ 4" BRASS CAP  
8" J. PINE N56°W 39 LKS  
5" B. OAK S41°W 56 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE/BRASS CAP  
8" J. PINE N56°W 25.7' NOW 10" DEAD J. PINE

A PERPETUATION OF THE ORIGINAL GOVERNMENT CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LEFT 1" PIPE/ MICH DEPT OF CONSERVATION BRASS CAP IN PLACE  
WIT: NAIL & TAG IN 12" J. PINE S45°W 58.83'  
NAIL & TAG IN 5' W. PINE N70°E 2.6'  
NAIL & TAG IN 17" TW B. OAK S65°E 16.88'  
NAIL & TAG IN 4' W. PINE N87°W 20.33'  
WITNESS POST NORTH 1.1'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

CRAWFORD COUNTY  
PEER GROUP APPROVAL  
DATE Sept 10, 1999

*Marvin E. Myers*  
Marvin E. Myers, P.S.  
County Surveyor



Signed by *Larry L. Cavanagh*  
Surveyor's Michigan License NO. 17614

Date Sept. 14, 1999