

SURVEY & REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26NR 4W</u>	<u>F-13</u>
	T <u>25 R 4W</u>	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	
4. Lot No. _____, Recorded Plat _____	LIBER	
5. Private Claims _____		

STATE OF MICHIGAN
CRAWFORD COUNTY
RECORDED
19 DEC 97 2:39 P.M.
SANDRA MOORE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

3 PAGE 295

	A	B	C	D	E	F	G	H	I	J	K	L	P
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin E. Myers, in a field survey on September, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O.
April 16, 1839
H. Brevoort D.S. & James H. Mullet D.S
MON: Post
WIT: 20" Yellow Pine N28°W 50 links
30" Yellow Pine N81°E 10 links

Michigan Department of Conservation
Billy D. Buckler; October 25, 1956
Found Both probable original BT's in place
Found evidence of old stake point in digging.
MON: 1" pipe with 4" Brass cap
WIT: 5" White Oak N37°E 9 links
6" White Oak S05°E 7 links

CRAWFORD COUNTY
PEER GROUP APPROVAL
DATE Oct 16, 1997
Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" pipe with Conservation Department cap. Left in place.
Found 8" White Oak with blaze and set nail and tag in East face N45°E 5.76'
Found Pine stump N80°E 7' to face
Accepted as a perpetuation of the Original Government Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Mon - Existing conservation Department monument left in place.
Set nail and tag in West face 6" Red Oak N28°W 12.37'
Set nail and tag in North face 4" Red Oak S68°W 13.05'
Set nail and tag in East face 12" White Oak South 4.90'
Set Carsonite Post North 1'

Signed by Marvin E. Myers
Surveyor's Michigan License No. 31600

Date Oct 16, 1997

