

JAN 04 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Crawford Located In: Corner Code #
 (County)

1. Public Land Survey T 26N R 4W K-3
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 CRAWFORD COUNTY
 RECORDED
 17 AUG 99 12:32 P.M.
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 4 PAGE 17

I, Marvin E. Myers, in a field survey on February 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3			2		1	
3													
4	7		8		9		10			11		12	
5													
6	18		17		16		15			14		13	
7													
8	19		20		21		22			23		24	
9													
10	30		29		28		27			26		25	
11													
12	31		32		33		34			35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O - 1852, Addison Brewer. D.S. Mon. - Post 8" Y. Pine N33°30'E 22 lks. 6" Hemlock S74°W 12 lks.	George D. Henning R.L.S. Retracement & restoration survey dated 1959 Mon: 1/2" iron & Post Wit: 18" Norway S56°W 56.4' 18" Norway S30°W 52.2'	Norman F. Parker, R.L.S. #16939 L.C.R.C. Liber 1, page 157 Mon: 1/2" bar By G.D. Henning 1957 Wit: 18" Norway Pine S56°W 56.4' 18" Norway Pine S76°E 75.4'
Norman F. Parker, R.L.S. #16939 Liber 151, Page 447 survey dated 1974 Mon: concrete monument Wit: none provided	Norman F. Parker, R.L.S. #16939 Liber 170, Page 555 survey dated 1978 Mon: 1/2" bar Wit: 18" Norway Pine S56°W 56.4' 18" Norway Pine S76°E 75.4'	Norman F. Parker, R.L.S. #16939 Liber 219, Page 359 survey dated 1983 Mon: 1/2" bar Wit: 18" Norway Pine S56°W 56.4' 18" Norway Pine S76°E 75.4'
Norman F. Parker, R.L.S. #16939 Liber 235, Page 273 survey dated 1985 Mon: 1/2" bar Wit: 18" Norway Pine S56°W 56.4' 18" Norway Pine S76°E 75.4'		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2"x18" iron of record 16' East of edge of water (corner falls on the East river bank of the AuSable river) in line with trail road East and the west edge of existing 8' trail road South. Found 18" Norway Pine S56°W 56.5', Found 18" Norway Pine S76°E 73.4'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Mon: Set standard county corner
 Wit: Spike in N. face 8" Norway Pine S72°E 12.3'
 Spike in S. face 12" Oak S64°W 21.40'
 Spike in S. face 8" Oak S59°E 44.18'
 Spike in E. face 10" Oak S20°E 34.26'

CRAWFORD COUNTY
PEER GROUP APPROVAL
 DATE June 7, 1999
Marvin E. Myers
 Marvin E. Myers, P.S.
 County Surveyor
 Date June 9, 1999

Signed by Marvin E. Myers
 Surveyor's Michigan License No. 31600

