

**APR 07 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

<u>Crawford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	√ T <u>26NR 4W</u> √ T <u>25N R 4W</u> T _____ R _____ T _____ R _____	<u>K-13</u> <u>K-1</u> _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

STATE OF MICHIGAN  
 CRAWFORD COUNTY  
 RECORDED  
 19 DEC 97 2:39 P.M.  
 SANDRA MOORE  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

**LIBER**

**3 PAGE 300**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on September, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. April 16, 1839 Robert T. Ostling R.L.S. # Survey of Section 1, T25N, R4W
  - H. Brevoort D.S. & James H. Mullet D.S. Mon: Post Wit: 12" Hemlock N63E 56 links 18" Beech N46 1/2E 28 links December 1960 Mon: Iron beneath pavement Wit: None provided
  - Norman F. Parker R.L.S. #16939 LCRC Liber 2, Page 260 Aug 10, 1981 Mon: 1/2" over iron pipe in blacktop Wit: 12" Maple N52E 53.6' 8" Jack Pine S46W 95.6' Norman F. Parker R.L.S. P31 #16939 L191 P315 Aug. 27, 1980 Mon: 1/2" Iron "G.D. Henning" Wit: 12" Maple N52E 53.6' 10" Jack Pine S46W 95.6'
  - Norman F. Parker R.L.S. #16939 L191P09 Aug. 27, 1980 Mon: 1/2" Iron "G.D. Henning" Wit: 12" Maple N52E 53.6' 10" Jack Pine S46W 95.6' Norman F. Parker R.L.S. #16939 L206 P115 Aug. 10, 1981 Mon: 1/2" Iron "G.D. Henning" Wit: 12" Maple N52E 53.6' 10" Jack Pine S46W 95.6'
  - Norman F. Parker R.L.S. #16939 L217 P 624 June 22, 1983 Mon: 1/2" Iron Wit: No witnesses provided Norman F. Parker R.L.S. #16939 L 244 P 503 Nov. 25, 1985 Mon: 1/2" Iron over larger iron Wit: No witnesses provided

**CRAWFORD COUNTY**  
**PEER GROUP APPROVAL**  
 DATE Oct 16, 1997  
*Marvin E. Myers*  
**Marvin E. Myers, P.S.**  
 County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1/2" Iron; overtop of 1/2" Iron 2.3 feet deep (left this Iron in place). Found dead 12" maple with blaze at base N52°E 53.6'; Found 16" Jack Pine with blaze and "G. D. Henning" tag S46°W 95.6'. Accepted 1/2" Iron as the best available evidence of the position of the Original Corner.  
 Replaced with Standard Crawford County Monument in pavement monument box.

C. Description of monument for corner and accessories established to perpetuate location and position of the corner:  
 Mon - Standard Crawford County Monument in pavement monument box.  
 Wit: Set nail & tag in NW side Utility Pole Az. 233° 42.70  
 Set nail & tag in SW side Fence Corner Post Az. 145° 46.65  
 Set nail & tag in SE side 14" Red Pine Az. 63° 80.18  
 Found nail & tag 16" Jack Pine S46°W 95.60

Signed by Marvin E. Myers  
 Surveyor's Michigan License No. 31600

Date Oct 16, 1997

