

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26. NR. 4. W. . .

----- Crawford ----- COUNTY

DESCRIPTION OF CORNER . . . Corner common to Sections 3, 4, 9, 10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 8" Cedar - S52W - 24 links

6" Cedar - N2E - 40 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Corner is set from original BTs, the SW White Pine longbutt in place with both faces and partial scribe marks.
A concrete filled tile at corner, also.

Corner was placed and witnessed 5/12/56

SURVEYORS SEAL

SIGNED *Billy D. Buckles* DATE 5/17/56
REGISTERED LAND SURVEYOR