

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR 4 W  
25 NR 5 W  
26 NR 4 W  
26 NR 5 W Crawford  
Kalkaska COUNTY

DESCRIPTION OF CORNER Corner common to sections 1, 6, 31, 36

DESCRIPTION OF CORNER MONUMENT 4" pipe with 4" brass cap

WITNESSES TO CORNER

12" B. Oak - N5W - 21 links  
10" B. Oak - S57E - 51½ links  
8" B. Oak - S17W - 128 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of these townships. Found a concrete filled field tile at corner, presumed to have been set by County Surveyor Houghton. No evidence of OBTs but corner checks good for measurement in four directions.

Corner was placed and witnessed Dec. 21, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 12/26/56  
REGISTERED LAND SURVEYOR