

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 4 W. . . .

----- Crawford ----- COUNTY

DESCRIPTION OF CORNER Witness corner for Meander corner between Sections 8 & 17

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap
Set 23 links west of true M.O.

WITNESSES TO CORNER Witnesses to witness corner

18" R. Pine - N22W - 48 links

18" R. Pine - S48W - 66 links

8" Maple - S18W - 10 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found an old stake scribed M.P. on bank of lake 23 links west of position of probable original Meander corner, which would now fall in water. From probable position of government M.P. a 9" W. Pine stump with good face, scribed NBT bears S48W 15 links, and is being washed out by water action. Roots of possible NW BT in place, but stump is gone.

Corner was placed and witnessed September 5, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 10/30/57
REGISTERED LAND SURVEYOR